Date: 04.01.2019

Revised BoQ - Amendment 2

1. AMI BOQ

SI. No	Item Description	Unit	Quantit
	Makes Occupie		
Α	Meter Supply		
1.	Single phase whole current Smart Meter 5-30A with provision of RF/GPRS/3G/4G Communication Module alon with associated Power Supply as per specifications (Subject to maximum of 10% allowed on GPRS after Approval of Employer)	Nos.	34000
1A	Single phase whole current Smart Meter 10-60A with provision of RF/GPRS/3G/4G Communication Module alon with associated Power Supply as per specifications (Subject to maximum of 10% allowed on GPRS after Approval of Employer)	Nos.	136000
2.	Three Phase whole current Smart Meter 20-100A RF/GPRS/3G/4G Communication Module and associated Power Supply as per specifications (Subject to maximum of 10% allowed on GPRS after Approval of Employer)	Nos.	30000
2A	Common Meter Reading Instrument/Tablet compatible with all type of Smart Meters with all desired communication facilities to enable downloading of parametres from Meters on Pole through wireless communication alongwith accessories	Nos.	112
В	Meter Box Supply:	l	
3.	Meter Box (1:1) along with mounting clamps, nuts & bolts for 1-Ph Meter	Nos.	25500
4.	Meter Box (2:1) with Bus Bars, internal wiring of appropriate current rating & connections along with mounting clamps, nuts & bolts for 1-Ph Meter	Nos.	21250
5.	Meter Box (4:1) with Bus Bars, internal wiring of appropriate current rating & connections along with mounting clamps, nuts & bolts for 1-Ph Meter	Nos.	25500
6.	Meter Box (1:1) along with mounting clamps, nuts & bolts for 3-Ph Meter	Nos.	30000
7.	Polycarbonate Seals for Meter Box as per Specifications		660000
С	Service Cable Supply & Service		
8.	2C x 25 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from LT ABC/Conductor to Single phase Meter Box (1:1) (Supply & Installation O/H) including all Terminations	Mtrs	76500
8A.	2C x 25 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from LT ABC/Conductor to Single phase Meter Box (2:1) (Supply & Installation O/H) including all Terminations	Mtrs	63750
9.	2C x 35 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from LT ABC/Conductor to Single phase Meter Box (4:1) (Supply & Installation O/H) including all Terminations	Mtrs	76500
10.	4C x 16 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from LT ABC/Conductor to Three phase Meter Box (1:1) (Supply & Installation O/H) including all Terminations	Mtrs	81000
11.	4C x 25 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from LT ABC/Conductor to Three phase Meter Box (1:1) (Supply & Installation O/H) including all Terminations	Mtrs	9000
12.	2C x 10 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from Single phase Meter Box (1:1, 2:1 & 4:1) to Consumer Premises (Supply & Installation) including all Terminations	Mtrs	204000
12.	2C x 16 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from Single phase Meter Box (1:1, 2:1 & 4:1) to Consumer Premises (Supply & Installation) including all Terminations	Mtrs	714000
13.	2C x 25 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from Single phase Meter Box (1:1, 2:1 & 4:1) to Consumer Premises (Supply & Installation) including all Terminations	Mtrs	102000
14.	4C x 16 sq.mm. Aluminium FRLS LT XLPE unarmoured Cable from Three phase Meter Box (1:1) to Consumer Premises (Supply & Installation) including all Terminations	Mtrs	162000

15.	4C x 25 sq.mm. Aluminium LT XLPE unarmoured Cable from Three phase Meter Box (1:1) to Consumer Premises (Supply & Installation) including all Terminations	Mtrs	18000
16.	Service main clamps for supporting service cable	Nos.	400000
17.	IPC with Aluminium Alloy connector for 1 phase meters connection from LT ABC	Nos.	101150
18.	IPC with Aluminium Alloy connector for 3 phase meters connection from LT ABC	Nos.	84000
19.	Mini Wedge Connector Suitable for Termination of Cable from Bare O/H Conductor to Meter Box	Nos.	43350
20.	Mini Wedge Connector Suitable for Termination of Cable from Bare O/H Conductor to Meter Box	Nos.	36000
D	Network Equipments - Supply & Service	•	
21.	DCU, Field Router, Collector and other associated Network Components required for Communication from Meter along with Installation Clamp and Accessories -Complete suitable for entire geographical area of Jammu and Srinagar City	LS	1
22.	Network Interface Card (NIC) for Meters	Nos.	200000
E	Meter Installation Services		
23.	Installation /Fixing and Commissioning of Meter Box (1:1) & Associated Pole clamp, accessories,Internal Wiring and complete sealing	Nos.	25500
24.	Installation /Fixing and Commissioning of Meter Box (2:1) & Associated Pole Clamp, accessories ,Internal wiring and complete sealing	Nos.	21250
25.	Installation /Fixing and Commissioning of Meter Box (4:1) & Associated Pole Clamp, accessories ,Internal wiring and complete sealing	Nos.	25500
26.	Installation /Fixing and Commissioning of Single Phase Smart Meter along with Associated accessories and complete sealing in Meter Box.	Nos.	170000
27.	Installation /Fixing and Commissioning of Three Phase Smart Meter along with Meter Box with Associated accessories and complete sealing	Nos.	30000
F	Dismantling Services	•	
28.	Removal of Single Phase old Meter & Return Back to JKPDD Store along with Removed Accessories	Nos.	170000
29.	Removal of Three Phase old Meter & Return Back to JKPDD Store along with Removed Accessories	Nos.	30000
30.	Removal of 2 Core cable/Wires & Return Back to JKPDD Store along with Removed Accessories	Mtrs	1020000
31.	Removal of 4 Core Cable/Wires & Return Back to JKPDD Store along with Removed Accessories	Mtrs	180000

2. BoM - IT Systems

SI. No	Item Description	Unit	Quantity
Α	Application Software		
A.1	Supply, Installation, Configuration & Integration of HES Software suitable for 2 Lakh Smart Meters	Lot	1
A.2	Installation, Integration & Customization - Oracle Utilities MDMS to the latest release of Oracle MDMS along with complete scope as detailed in IT Scope of work Amendment 2	Lot	1
	Sub Total (A) for Application Software		
В	Data Archiving Software		
B.1	Supply, Installation, Configuration & Integration of Data Archiving and SAN management software	Lot	1
С	Network Management Software		
C.1	Supply, Installation and Commissioning of Centralized Network Management Software along with patch management & identity management	Lot	1
C.2	Supply and Installation of Antivirus software for all machines in control centre	Lot	1
D	Supply, Installation & Commissioning of Hardware for application		
D.1	Application & DB Server suitable for HES Software Application High Availability Active-Active Mode for DC & DR both	Lot	1

D.2	Application & DB Server suitable for Oracle MDM 2.2 Software Application High Availability Active-Active Mode for DC & DR both(sizing suitable for 20 Lakh consumers).	Lot	1
D.3	Supply, Installation & Commissioning of Development/Quality Testing Server for HES Application at DC only	Lot	1
D.4	Supply, Installation & Commissioning Development / Quality testing Server for MDM Application at DC only	Lot	1
D.5	Supply, Installation, Configuration & Integration of Web Server for access for DC and DR both	Lot	1
Е	Supply, Installation & Commissioning of Hardware for storage		-
E.1	Supply, Installation, Configuration & Integration of SAN based storage capable to store 5 years Smart Meter data of 20 lakh consumers from HES/MDM for DC & DR both(Minimum storage capacity of 25TB or more, as per sizing requirement of the bidder)	Lot	1
E.2	Supply, Installation & Commissioning of Data Archiving Server for DC & DR both	Lot	1
F	Supply, Installation & Commissioning of Hardware for network Management	•	
F.1	Network Management server with patch & identity management	Set	1
F.2	Centralized management console with single 24" monitor with required Software (OS)	Set	1
G	Workstation Consoles		
G.1	Supply, Installation & Commissioning of Workstation consoles with dual 24" monitor along with Operating System & license	Nos.	8
Н	Network Hardware		-
H.1	Supply, Installation & Commissioning of Firewall with Network-based Intrusion Prevention System (NIPS) Minimum 8 Ethernet ports (1 Gbps) and 4 Fiber Optics Ports for DC & DR or higher suitable for proposed solution		1
H.2	Supply, Installation & Commissioning of Router with Minimum 8 Ethernet ports (1 Gbps) and 4 Fiber Optic Ports for DC & DR or higher suitable for proposed solution	lot	1
H.3	Supply, Installation & Commissioning of Application Load Balancer for DC suitable for proposed solution	lot	1
H.4	Supply, Installation & Commissioning of LAN Switch (minimum 24 port 1000 / 100 /10 Mbps, layer 3 switching, 8 Ethernet ports (1 Gbps) for DC & DR or higher suitable for proposed solution	lot	1
Note	SIM cards for Meters on GPRS(maximum of 10% of total quyantity subject to approval) & Communication from DCU to HES Backhaul will be provided by JKPDD		
I	Training	lot	1
J	FMS		
J1	FMS/AMC for 1st Year	Year	1
J2	FMS/AMC for 2nd Year	Year	1
J3	FMS/AMC for 3rd Year	Year	1
J4	FMS/AMC for 4th Year	Year	1
J5	FMS/AMC for 5th Year	Year	1

Note:

will be based on Total price of Supply & Service portion

- >The quoted rates must be inclusive of all taxes as applicable at the time of bidding.
- >Bidders are to quote their rates strictly as per above format.
- >Bidders has to fill the rates in all sub-sheets of excel file as per the format.
- >Any increase or decrease in applicable GST rates shall be paid or deducted accordingly
- > Above Bill of Material and Bill of Quantity is indicative. Bidder to quote price of items considering the overall solution requirement after assessing the utility requirement.
- > All the itemized price break up of lot supply to be provided after price bid opening.